



### INSTALLATION OF VERTICAL CONSTRUCTION JOINT (CJ) OR COLD JOINT

- [1] - ERECT CONFORMS AND REINFORCEMENT WITH THE CONSTRUCTION JOINT LOCATED TO SUIT A BOX CONNECTOR AT THE END OF THE WALL.
- [2] - INSTALL 5/8" PLYWOOD FULL HEIGHT IN THE BOX CONNECTOR LEGS. CUT PLYWOOD TO FIT TIGHT
- [3] - PROVIDE BRACING AT END OF WALL TO RESIST LATERAL CONCRETE PRESSURES.
- [4] - PLACE CONCRETE IN CONFORMS
- [5] - AFTER THE CONCRETE IS SET, REMOVE THE BRACING AND PLYWOOD. CHIP THE EXCESS CONCRETE AT THE WEB OF THE BOX CONNECTOR SO THAT THERE ARE NO PROJECTIONS BEYOND THE FACE OF THE WEB. CLEAN THE BOX CONNECTOR LEGS SO THAT THE ADJACENT PANEL WILL SLIDE INTO PLACE
- [6] - PRE-DRILL HOLES IN THE CONCRETE WALL TO SUIT HORIZONTAL DOWELS AS SPECIFIED BY THE STRUCTURAL ENGINEER. HOLE LOCATIONS MUST SUIT CORING IN CONFORM WEB.
- [7] - ERECT A SHORT SECTION OF CONFORMS TO EXTEND JUST BEYOND THE LAP, AS SPECIFIED BY THE STRUCTURAL ENGINEER, FOR THE DOWEL.
- [8] - INSTALL DOWELS THROUGH THE WEB CORING AND EPOXY GROUT INTO THE PREDRILLED HOLES AS SPECIFIED BY THE STRUCTURAL ENGINEER.
- [9] - ERECT CONFORMS AND REINFORCEMENT FOR CONTINUATION OF WALL.

- DETAIL FOR FORMWORK ONLY

- ALL DETAILS, REINFORCING STEEL & CONCRETE MUST BE DESIGNED & CONFIRMED BY PROJECT STRUCTURAL ENGINEER AND / OR PROJECT ARCHITECT.



Nuform Building Technologies Inc.  
1 Regalcrest Court,  
Woodbridge, Ontario, Canada L4L 8P3  
Tel: 905-652-0001 Fax: 905-652-0002  
Toll Free: 1-877-747-9255  
Web Page: www.nuformdirect.com

### CONFORM WALL - CONSTRUCTION JOINT



DRAWING NO.

T061

COPYRIGHT 2008

SCALE:

N/A

REVISION No.:

R00